BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 61

Name of Work:-Improvements of roads in Ananthpura Dhobighat of Attur ward no:03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri .CHENNAKRISHNA P	
				Rate	Rate in Words
1	KSRRB 200-8:-Clearing and grubbing road land including uprooting rank vegetation,grass,brush,shrubs,saplings and trees of girth up to 300mm,by manual means,in area of light jungle,removal of stumps,disposal of unserviceable materials,stacking of serviceable materials labour charges complete as per specifications (P NO132/18.12,PWD SR 2014-15)	sqm	990.00	8.00	Rupees eight only
2	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 138/ Item No. 19.1/ PWD SR 2012-15	Cum	247.50	104.00	Rupees one hundred four only
3	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in **hard soil** not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, **No. 5/ Item No. 2.4/ PWD SR 2014-15**	Cum	64.80	240.00	Rupees two hundred forty only
4	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2014-15)	Cum	312.30	60.00	Rupees sixty only
4	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murrum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) MORTH Specification No. 305. **(Page No. 144 & Item No. 19.60)**	Cum	248.40	200.00	Rupees two hundred only

Assistant Controller (Finance)

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri .CHENNAKRISHNA P	
				Rate	Rate in Words
6	Construction of granular sub-base by providing coarse graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve thedesired density, complete as per clause 401 of MORT & H For Grading-II Materia(PWD SR2014-15, P.NO151/20.5.2)	Cum	207.00	1073.00	Rupees one thousand seventy thr only
7	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete do 7.5 cms thick	Sqm	297.00	600.00	Rupees six hundred only
8	KSRRB M1400-14.2. Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding Materials to fill up the interstices of coarse aggregate, watering and compacting to the required density. Material Using Scrining Crushable Type such as Moorum or Gravel Grading - III (Manual) Clause : 404 (P.143/I.20.15.3 PWD SR - 2014-15).	Sqm	82.80	1616.00	Rupees one thousand six hundre eighteen only

P. chennakrishna

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.